# **PCT**

# WORLD INTELLECTUAL PROPERTY ORGANIZATION International Bureau




# INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(51) International Patent Classification 7:		(11) International Publication Number: WO 00/54661
A61B 17/00	A1	(43) International Publication Date: 21 September 2000 (21.09.00)
(21) International Application Number: PCT/US (22) International Filing Date: 17 March 2000 (		CH, CY, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC,
(30) Priority Data: 09/271,094 09/274,790 09/428,698 17 March 1999 (17.03.99) 23 March 1999 (23.03.99) 27 October 1999 (27.10.99)	Ţ	Published  With international search report.  US  US
(71) Applicant: ANGIOTRAX, INC. [US/US]; 743 N Avenue, Sunnyvale, CA 94086 (US).	. Pasto	ria
(72) Inventor: SAADAT, Vahid; 1 Avocet Drive #204, Shores, CA 94065 (US).	Redwo	od
(74) Agents: PISANO, Nicola, A. et al.; Fish & Nea Avenue of the Americas, New York, NY 10020 (	ave, 12 (US).	51
(CA) TAIL. ADDADATES AND METHODS FOR DEDE		NG PERCUTANEOUS MYOCARDIAL REVASCULARIZATION AND

(54) Title: APPARATUS AND METHODS FOR PERFORMING PERCUTANEOUS MYOCARDIAL REVASCULARIZATION AND STIMULATING ANGIOGENESIS USING AUTOLOGOUS MATERIALS

#### (57) Abstract

Methods are provided for collecting, and processing autologous biological materials to form autologous angiogenic agents. Apparatus (30), and methods also are provided for performing percutaneous myocardial re-vascularization wherein an injection needle (32) is disposed in spaced-apart relation to the channel forming tool (31) so that a predetermined amount of the autologous angiogenic agent may be injected into the myocardium (M) adjacent to the PMR channel (C).



# FOR THE PURPOSES OF INFORMATION ONLY

Codes used to identify States party to the PCT on the front pages of pamphlets publishing international applications under the PCT.

AL Albania ES Spain LS Lesotho SI Slovenia AM Armenia FI Finland LT Lithuania SK Slovekia AT Austria FR France LU Luxembourg SN Senegal AU Australia GA Gabon LV Latvia SZ Swaziland AZ Azerbaijan GB United Kingdom MC Monaco TD Chad AZ Azerbaijan GB United Kingdom MC Monaco TD Chad BA Bosnia and Herzegovina GE Georgia MD Republic of Moldova TG Togo BA Bosnia and Herzegovina GF Ghana MG Madagascar TJ Tajikistan BB Barbados GH Ghana MK The former Yugoslav TM Turkmenistan BE Belgium GN Guinea MK The former Yugoslav TM Turkrenistan BF Burkina Faso GR Greece Republic of Macedonia TR Turkey BF Burkina Faso HU Hungary ML Mali TT Trinidad and Tobago BJ Benin IE Ireland MN Mongolia UA Ukraine BJ Benin IE Ireland MR Mavritania UG Uganda BR Brazil IL Israel MR Mavritania UG Uganda CC Canada IT Italy MX Mexico UZ Uzbekistan CC Canada IT Italy MX Mexico UZ Uzbekistan CC Congo KE Kenya NL Netherlands YU Yugoslavia CC Congo KE Kenya NO Norway ZW Zimbabwe  CC Congo KE Kenya NO Norway ZW Zimbabwe  CC Congo KE Kenya NO Norway ZW Zimbabwe  CC Cote d'Ivoire KP Democratic People's NZ New Zealand CC Cuba KZ Kazakstan RO Romania CC Cuba KZ Kazakstan RO Romania CC Cache Republic LC Saint Lucia RU Russian Federation CC Cache Republic LC Saint Lucia SC Singapore	VS Vanetho SI Slovenia		<del>-</del>							
	AL Albania ES Spain L3 Leboth SK Slovakia AM Armenia FI Finland LT Lithuania SK Slovakia AM Armenia FI Finland LT Lithuania SK Senegal AT Austria FR France LU Luxembourg SN Senegal AT Austria GA Gabon LV Latvia SZ Swaziland AU Australia GA Gabon MC Monaco TD Chad AZ Azerbaijan GB United Kingdom MC Monaco TD Chad TD Chad AZ Azerbaijan GB GB United Kingdom MD Republic of Moldova TG Togo BA Bosnia and Herzegovina GE Georgia MD Republic of Moldova TG Togo BB Barbados GH Ghana MK The former Yugoslav TM Turkmenistan TR Turkey BF Burkina Faso GR Greece Republic of Macedonia TR Turkey BF Burkina Faso HU Hungary ML Mali TT Trinidad and Tobago UA Ukraine BJ Benin IE Ireland MN Mongolia UA Ukraine BJ Benin II Israel MR Mauritania UG Uganda BB Brazil II Israel MR Mauritania UG Uganda UA Ukraine CA Canada IT Italy MX Mexico UZ Uzbekistan CA Canada IT Italy MX Mexico UZ Uzbekistan CCA Canada IT Italy MX Mexico UZ Uzbekistan CCG Congo KE Kenya NL Netherlands YU Yugoslavia CCG Congo KE Kenya NL Netherlands YU Yugoslavia CCH Switzerland KG Kyrgyzstan NO Norway ZW Zimbabwe CCH Cameroon KR Republic of Korea PL Poland CCN China KR Republic Sco Singapore	AM AT AU AZ BA BB BE BF BG BJ CA CF CG CH CI CM CN CU CZ DE	Armenia Australia Australia Azerbaijan Bosnia and Herzegovina Barbados Belgium Burkina Faso Bulgaria Benin Brazil Belarus Canada Central African Republic Congo Switzerland Côte d'Ivoire Cameroon China Cuba Czech Republic Germany Denmark	FI Finland FR France GA Gabon GB United GE Georgi GH Ghana GN Guiner GR Greece HU Hunga IE heland IL Israel IS Icelan IT haly JP Japan KE Kenya KG Kyrgy KP Democ Repul KR Repul KZ Kazal LC Saint LI Liece LK Sri L	and be	LT LU LV MC MD MG MK MI MN MN MN MR NE NL NO NZ PL PT RO RU SE	Lithuania Luxembourg Latvia Monaco Republic of Moldova Madagascar The former Yugoslav Republic of Macedonia Mali Mongolia Mauritania Malawi Mexico Niger Netherlands Norway New Zealand Poland Portugal Romania Russian Federation Sudan Sweden	SK SN SZ TD TG TJ TM TR TT UA UG US VN YU	Slovakia Senegal Swaziland Chad Togo Tajikistan Turkmenistan Turktey Trinidad and Tobago Ukraine Uganda United States of America Uzbekistan Viet Nam Yugoslavia	

APPARATUS AND METHODS FOR PERFORMING PERCUTANEOUS MYOCARDIAL REVASCULARIZATION AND STIMULATING ANGIOGENESIS USING AUTOLOGOUS MATERIALS

# Field Of The Invention

5

20

The present invention relates to apparatus and methods for performing percutaneous myocardial revascularization and injecting autologous materials into the treated tissue to stimulate angiogenesis.

# Background Of The Invention

10 A leading cause of death in the United States today is coronary artery disease, in which atherosclerotic plaque causes blockages in the coronary arteries, resulting in ischemia of the heart (i.e., inadequate blood flow to the myocardium). The disease 15 manifests itself as chest pain or angina. In 1996, approximately 7 million people suffered from angina in the United States.

One technique that has been developed to treat patients suffering from diffuse atherosclerosis, is referred to as percutaneous myocardial

revascularization (PMR). In this method, a series of 5 channels are formed in the left ventricular wall of the heart extending inward from the myocardium. Typically, between 15 and 30 channels about 1 mm in diameter and preferably several millimeters deep are formed with a laser in the wall of the left ventricle to perfuse the 10 heart muscle with blood coming directly from the inside of the left ventricle, rather than traveling through the coronary arteries. Commonly assigned U.S. Patent No. 5,910,150 to Saadat describes mechanical apparatus for forming such channels. PCT Publication WO 98/17186 15 describes a laser-based system for performing PMR that includes needle adjacent to the laser element for injecting a contrast agent to mark the position of the PMR channels for imaging.

20

25

35

U.S. Patent No. 5,840,059 to March et al. describes a laser-based PMR system that deposits a angiogenic agent, such as a gene vector or genetically engineered harvested cells, into the channel formed during the PMR procedure to promote angiogenesis. A drawback of this approach, however, is that blood pulsing through the PMR channel during normal cardiac wall motion may cause the angiogenic factor to be promptly washed out of the channel, thereby dissipating any beneficial effect obtainable from its introduction. In addition, it is relatively difficult and expensive 30 to use engineer and produce the kinds of angiogenic factors referred to in the foregoing patent.

Accordingly, it would be desirable to provide apparatus and methods for delivering angiogenic agents in conjunction with PMR treatments that promote longterm residence of the angiogenic agent in the vicinity of the treated tissue. It further would be desirable to provide relatively low-cost and readily available or

- 3 -

5 readily prepared angiogenic agents for use in conjunction with PMR.

Wartiovaara et al., "Peripheral Blood Platelets Express VEGF-C and VEGF which Are Released During Platelet Activation," Thromb Haemost, 80:171-175 10 (1998), describes that a variety of vascular endothelial growth factors (VEGF) may be derived from platelets. Knighton et al., "Role of Platelets and Fibrin in the Healing Sequence," Ann. Surg., 196(4)379-388 (1982), which is incorporated herein by reference, 15 describes that thrombin-activated platelets, when injected in vivo in rabbit corneas, produced neovascularization that was dose related. U.S. Patent Nos. 4,957,742 to Knighton, U.S. Patent No. 4,479,896 to Antoniades, and U.S. Patent No. 5,834,418 to Brazeau 20 · describe methods of extracting platelet growth factors from blood.

Sakai et al., "Autologous Cardiomyocyte
Transplantation Improves Cardiac Function After
Myocardial Injury," presented at the 1999 STS
Convention, San Antonio, New Mexico, January 1999,
suggests that autologous cardiomyocytes may be
harvested, cultured and re-injected into injured
myocardium to restore ventricular function.

25

30

In view of the foregoing, it would be desirable to provide apparatus and methods for using autologous materials in conjunction with PMR to augment angiogenesis resulting from forming myocardial channels.

It further would be desirable to provide

apparatus and methods that reduce the risk of such
autologous angiogenic materials from washing out of the

PMR channels, and instead promote retention of such
materials by injecting the angiogenic materials into

- 4 -

5 the myocardium adjacent to the PMR channels.

# Summary Of The Invention

10

15

20

25

30

35

In view of the foregoing, it is an object of this invention to provide apparatus and methods for delivering angiogenic agents in conjunction with PMR treatments that promote long-term residence of the angiogenic agent in the vicinity of the treated tissue.

It is another object of the present invention to provide apparatus and methods for conveniently and economically preparing autologous angiogenic agents for use in conjunction with PMR.

It is another object of this invention to provide apparatus and methods for using autologous materials in conjunction with PMR to augment angiogenesis resulting from forming myocardial channels.

It is also an object of the present invention to provide apparatus and methods that reduce the risk of such autologous angiogenic materials from washing out of the PMR channels, and instead promote retention of such materials.

It is a further object of the present invention to provide apparatus and methods for performing percutaneous myocardial revascularization that enable autologous angiogenic agents, such as platelets, platelet derived growth factors or cardiomyocytes to be injected into the myocardium adjacent to the PMR channels.

These and other objects of the present invention are accomplished by providing methods for collecting and processing autologous biological materials to form autologous angiogenic agents.

Apparatus and methods also are provided for performing percutaneous myocardial revascularization that includes

- 5 -

an injection needle disposed in spaced-apart relation to the channel-forming tool, so that a predetermined amount of the autologous angiogenic agent may be injected into the myocardium adjacent to the PMR channel.

In accordance with the principles of the present invention, blood, cardiomyocytes, or other biological material is first collected from a patient scheduled to undergo PMR. The biological material is then treated to concentrate and activate or express one or more platelet derived growth factors, and is stored in preparation for re-injection into the patient's myocardium during a PMR procedure.

20

25

30

35

Apparatus suitable for implementing the methods of the present invention comprises a catheter having an end region that is directable to contact a patient's endocardium at a plurality of positions. Preferably, the catheter comprises inner and outer catheters each having preformed distal bends, so that the distal end of the inner catheter is directable to a plurality of positions. A cutting head is disposed within a lumen of the inner catheter and coupled to a drive tube that rotates and reciprocates the drive shaft. The drive tube is coupled to a motor that imparts rotational motion to the drive tube. The cutting head and drive tube include a lumen through which severed tissue is aspirated.

One or more stabilizing elements, are disposed on the distal end to retain the inner catheter in position while the cutting head is reciprocated beyond a distal endface of the inner catheter. In accordance with the present invention, the stabilizing elements also serve as injection needles for the reinjecting autologous angiogenic agent into the

- 6 -

patient's myocardium in the vicinity of the channels 5 formed by the cutting head. Methods of using the apparatus to deliver angiogenic agents also are described.

#### Brief Description Of The Drawings 10

15

20

25

30

35

Further features of the invention, its nature and various advantages will be more apparent from the accompanying drawings and the following detailed description of the preferred embodiments, in which:

FIG. 1 is a flow chart illustrating steps of collecting and processing blood to prepare autologous angiogenic agents;

FIG. 2 is a flow chart for an alternative method of the present invention wherein cardiomyocytes are collected and processed for re-injection into a patient's myocardium;

FIG. 3 is an illustrative view of a distal end of apparatus of the present invention injecting boluses of autologous angiogenic material adjacent to channels formed by the device;

FIG. 4 is a perspective view of an illustrative embodiment of apparatus suitable for implementing the methods of the present invention;

FIG. 5 is a partial sectional view of the distal region of the apparatus of FIG. 1;

FIG. 6 is a perspective view illustrating how the inner and outer catheters can be rotated to position the distal end of the inner catheter at a plurality of positions;

FIGS. 7A and 7B are, respectively, a perspective view and sectional view of an illustrative handle of the apparatus of FIG. 4;

FIG. 8 is a block diagram of the components of a controller constructed in accordance with the

- 7 -

## 5 present invention; and

FIGS. 9A-9C are views illustrating deployment and use of the apparatus of FIG. 3 to percutaneously form channels in the myocardium and inject autologous angiogenic agents.

10

15

20

25

30

35

## Detailed Description Of The Invention

The present invention provides methods for collecting and preparing autologous biological materials to form angiogenic agents, and apparatus for injecting those angiogenic agents into a patient's myocardium in the vicinity of channels formed by PMR. In accordance with the methods of the present invention, a series of channels is cut into the myocardium using a rotating cutting head through which severed material is aspirated. A stabilizer element fixed in a spaced-apart relation to the cutting head is employed to inject the autologous angiogenic material into pockets in the vicinity of the PMR channel. Advantageously, the angiogenic material disposed within pockets may migrate to towards the PMR channels to enhance revascularization, without being washed out of the PMR channel as in previously known methods.

Referring to FIG. 1, a first illustrative method of providing autologous angiogenic agents is described. A patient scheduled for a PMR procedure arranges to visit the hospital or clinic where the procedure is to be performed several days in advance of the procedure, and a quantity of whole blood is collected at step 10.

At step 11, the blood is then centrifuged using any of a number of previously known techniques, e.g., such as described in the foregoing patent to Knighton, to obtain a platelet rich plasma. The resulting platelet-rich plasma may be further

- 8 -

5 centrifuged, and the platelet concentrate resuspended in a buffered solution to a concentration of about a million platelets per milliliter or less.

At step 12, the platelets are activated using one of a number of known techniques, and preferably by being exposed to thrombin about 1 to 10 units of purified thrombin per ml of resuspended platelet material, again as described in the above-incorporated article by Knighton. At step 13, the resulting angiogenic agent is filled in appropriately sized vials for use in conjunction with the patient's PMR procedure and stored under refrigeration, until the day of the PMR procedure.

Other methods for preparing an angiogenic agent from the patient's blood also may be employed, as described in the above-referenced articles. It is sufficient for the method illustrated in FIG. 1 that, at the end of the collection and processing step, an angiogenic platelet-rich agent has been prepared, at a much lower cost than associated with the production of gene vectors such as described in the aforementioned March et al. patent.

20

25

30

35

Referring to FIG. 2, an alternative method of collecting and preparing an autologous angiogenic agent is described. In this method, prior to the date of a scheduled PMR procedure, the patient arranges to visit the hospital or clinic to have a number of cells harvested. For example, using the PMR device described in the aforementioned patent to Saadat, which is incorporated herein by reference, a quantity of myocardial cells may be harvested, at step 21. Alternatively, other suitable cells, such as bone marrow cells, may be extracted.

- 9 -

At step 22, the harvested cells are processed and prepared for use in conjunction with the subsequent PMR procedure. For example, the harvested cells may be cultured, using techniques which are per se known and described in the above-mentioned work of Sakai. At step 23, the harvested cells are then divided and suspended in an appropriately buffered solution. The resulting angiogenic agent is filled in appropriately sized vials and stored awaiting re-injection during the PMR procedure.

15

20

25

30

35

Referring now to FIG. 3, illustrative methods of injecting an autologous angiogenic agent in conjunction with PMR are described. In FIG. 3, distal end 30 of PMR apparatus, as described hereinbelow, is disposed adjacent to endocardium E in a patient's left ventricle. Reciprocable cutting head 31 of the PMR apparatus is used to bore channels C into myocardium M through the endocardial surface.

In accordance with the methods of the present invention, hollow reciprocable stabilizer needle 32 is used to inject a bolus of a predetermined quantity of autologous angiogenic agent into "pocket" P adjacent to channel C upon completion of the channel-forming operation of cutting head 31. Advantageously, the angiogenic agent is expected to migrate from the pocket P towards the channel over a period of time, thereby enhancing revascularization, but without having the angiogenic agent washed out of the channel during normal wall motion.

Referring now to FIGS. 4 and 5, illustrative apparatus 40 suitable for practicing the methods of the present invention is described. Apparatus 40 includes device 41 comprising handle 44 having inner catheter 43 disposed within outer guide catheter 42, and coupled to

5 controller 45 via cable 46 and vacuum hose 47. Cutting head 48 having lumen 49 and sharpened distal end 50 is disposed within lumen 51 of inner catheter 43. Cutting head 48 is coupled to drive tube 52, which in turn is coupled via cable 46 to a drive system contained in controller 45 that imparts rotational and longitudinal motion to drive tube 52 and cutting head 48. Suction is drawn through lumen 49 of cutting head 48 and drive tube 52 to aspirate tissue severed by the cutting head to tissue trap 53 connected to controller 45 via vacuum hose 47.

Vacuum canister (not shown) that draws suction through lumen 54 of drive tube 52 via hose 47, a drive train (not shown) including a motor and gearing that impart rotational motion to drive tube 52 via cable 46, and a linear actuator mechanism (e.g., electromechanical or pneumatic) that reciprocates drive tube 52 and cutting head 48 within lumen 51 of inner catheter 43.

Controller 45 also includes display panel 55, input panel 56 (e.g., a plurality of selector switches) and circuitry (see FIG. 7) for controlling operation of device 41. Further details of controller 45 are described in the above-incorporated patent to Saadat.

20

25

30

35

Inner catheter 43 is disposed for movement, either rotational, longitudinal or both, within lumen 57 of outer guide catheter 42. Inner catheter 43 further includes lumen 58 through which hollow needle stabilizer 59 may be reciprocated from a retracted position, within lumen 58, to an extended position, extending beyond distal endface 60 of inner catheter 43 (as shown in FIG. 5). A proximal end of hollow needle stabilizer 59 is coupled to slider button 61 of handle 44. When moved to the extended position, needle

- 11 -

5 stabilizer 59 retains the distal end of inner catheter 43 in position with respect to an endocardial surface, and counteracts reaction forces generated when cutting head 48 is actuated.

Cutting head 48 and drive tube 52 are coupled via cable 46 to a drive train that moves cutting head 10 48 from a retracted position within lumen 51 of inner catheter 43 (as shown in FIG. 5), to an extended position wherein cutting head 48 and a distal portion of drive tube 52 extend beyond distal endface 60 (see FIG. 6). Button 62 of handle 44 signals controller 45 15 to extend and rotate cutting head 48 to cut a channel in the myocardium. Myocardial tissue severed by cutting head 48 is aspirated through lumen 54 of drive tube 52 to tissue trap 53 to reduce the risk that the severed tissue will embolize. Cutting head 48 20 preferably is constructed of a radio-opaque material or includes band 65 of radio-opaque material, such as platinum-iridium, disposed on its proximal end to assist in visualizing the location of the cutting head under a fluoroscope. 25

Referring to FIG. 6, outer guide catheter 42 and inner catheter 43 preferably include preformed bends. In particular, by rotating outer guide catheter 42 (indicated by arrows A) or inner catheter 43 (as indicated by arrows B) relative to one another, or extending inner catheter 43 longitudinally with respect to outer guide catheter 42 (as indicated by arrows C), distal endface 60 of inner catheter 43 may be disposed at a plurality of tissue contacting locations.

30

Accordingly, outer guide catheter may disposed at a first orientation relative to an endocardial surface, and then inner catheter 43 may be moved relative to outer catheter 42 to form channels at a plurality of

positions along the path indicated by arrows B. Outer catheter 42 may then be moved along the path indicated by arrows A, and a new series of holes may then be formed at that position by further rotating inner catheter 43. As will of course be understood, needle stabilizer 59 and cutting head 48 are retracted when moving between one channel forming position and another.

Referring now to FIGS. 7A and 7B, an illustrative arrangement of the components of handle 44 is described. Handle 44 comprises proximal and distal portions 70 and 71, respectively, joined so that distal portion 71 may be rotated independently of proximal portion 70. Proximal portion 70 is coupled to cable 46 and includes button 62 for activating the cutting head to bore a channel. Distal portion 71 is affixed to inner catheter 43 so that rotation of knob 63 of portion 71 is transmitted to the distal end of inner catheter 43.

stabilizer 59, so that movement of button 61 in the distal direction deploys needle stabilizer 59, and movement of button 61 in the proximal direction retracts needle stabilizer 59 within lumen 58 of inner catheter 43. Needle stabilizer 59 includes a lumen through which the autologous angiogenic agent is injected, as described hereinabove, for example, by depressing button 61. Wheel 64, if provided, is coupled to inner catheter 43 to permit optional adjustment of the cutting depth attained by cutting head 48.

With respect to FIG. 7B, wheel 64 is disposed within tubular member 76 and extends within portions 70 and 71. Inner catheter 43 is coupled to a rigid

- 13 -

tubular member (e.g., stainless steel hypotube) that extends through element 77. Element 77 in turn is coupled through tubular member 78 to distal portion 71, so that rotation of distal portion 71 is transmitted to inner catheter 43. Tubular member 76 is coupled by threads to tubular member 78 so that rotation of wheel 64 causes inner catheter to be moved in a distal or proximal direction relative to drive tube 52 (depending upon direction of rotation), thereby lengthening or shortening the stroke of cutting head 48 beyond distal endface 60 of the inner catheter.

Drive tube 52 has proximal end 80 affixed to tubular member 81 having skive 82. Tubular member 81 is coupled to drive wire 83. Tubular member 81 is disposed for rotational and longitudinal motion, 20 imparted by drive wire 83, within tubular member 84. The distal end of tubular member 84 is disposed within tubular member 78, while the proximal end includes a suitable bearing that seals against tubular member 81 without binding. Tissue passing through lumen 54 of 25 drive tube 52 exits through skive 82 into the interior of tubular member 84, and then aspirated through port 85 into vacuum hose 47. Tubular member 84 is affixed to the interior of proximal portion 71 by element 86, which also supports button 62. Needle stabilizer 59 is 30 fastened to slider button 61, which is in turn coupled to spool 77 to provide rigidity to the assembly. Needle stabilizer also includes a port that permits the lumen of the needle to be coupled to a vial or syringe containing autologous angiogenic agent.

35 Handle 44 therefore provides the ability to rotate distal portion 71 of the handle to orient the bend in inner catheter 43, while retaining button 62 on top of proximal portion 70 facing upward. Slider

5 button 61 permits needle stabilizer 59 to be selectively deployed, and knob 63 permits the inner catheter to be rotated relative to the outer guide catheter. Wheel 64 permits the inner catheter to be translated distally or proximally with respect to the cutting head, to account for the effects of inserting the distal portion of device 41 along a tortuous path.

15

20

25

30

35

With respect to FIG. 8, a block diagram of the components of controller 45 are described. Controller 45 preferably comprises microprocessor 90 coupled to display panel 55, input device 56 (e.g., keyboard), activation button 62 of handle 44, data storage 91 (e.g., RAM and ROM or hard disk), vacuum pump 92, linear actuator mechanism 93 (e.g., a worm screw drive or pneumatic cylinder), motor 94 and monitoring circuitry 95. Monitoring circuitry 95 may be coupled to components 92-94, for example, to monitor the level of vacuum drawn by vacuum pump 92, or a motor parameter, such as the displacement of or linear force applied by linear actuator mechanism 93 and/or the speed of or electrical current drawn by motor 94.

For example, monitoring circuitry 95 may be arranged to ensure that the cutting head is not extended unless there is an appropriate level of suction being drawn through drive tube 52 and cutting head 48, or that the cutting head is rotating at a desired RPM before being advanced into tissue. Additional applications for monitoring circuitry 95 are described in the above-incorporated, commonly assigned U.S. patent.

Referring now to FIGS. 9A-9C, a method of using the apparatus of the present invention perform PMR and to inject autologous angiogenic agents is described. In FIG. 9A, distal region 100 of device 41

- 15 -

of FIG. 1 is shown positioned in a patient's left ventricular cavity, using techniques which are per se known. Specifically, distal region 100 of device 41 is inserted via a femoral artery, and is maneuvered under fluoroscopic guidance in a retrograde manner up through the descending aorta, through aortic arch A, and down through ascending aorta AA and aortic valve AV into left ventricle LV. Previously known imaging techniques, such as ultrasound, MRI scan, CT scan, or fluoroscopy, may be used to verify the location of the distal region 100 within the heart.

In FIG. 9B, slider button 61 on handle 44 is advanced to extend needle stabilizer 59 so that it penetrates into the myocardium a predetermined distance, for example, 7 mm. Button 62 on handle 44 then is depressed, causing the drive system of controller 45 to extend cutting head 48 to bore a channel into the myocardium to a predetermined depth. Alternatively, button 62 of handle 44 may be omitted, and controller 45 instead programmed so that linear actuator 93 causes the cutting head to be extended a predetermined interval of time (e.g., 1 second) after slider button 61 is actuated. In this alternative embodiment, slider button 61 will of course have to generate a signal that is communicated to controller 45 via cable 46.

20

25

30

35

When cutting head 48 engages the endocardium, a reaction force is generated in inner catheter 41 that tends both to push distal region 100 away from the tissue. Needle stabilizer 59 counteracts these reaction forces and reduces transverse movement of the distal end of inner catheter 43, thus retaining the inner catheter in position while the cutting head is extended and retracted. Tissue severed by the cutting

5 head is aspirated to trap 53 of controller 45.

10

15

20

25

30

35

Once cutting head reaches its maximum extension, as determined by any of the means described hereinabove, processor 90 causes forward motion of the cutting head to cease. In the embodiments using linear actuator 93, processor 90 also issues a command to reverse the direction of linear actuator 93. This in turn causes cutting head 48 to be withdrawn from channel C formed in the myocardium to a position just below distal endface 60 of inner catheter 43. Button 61 is then depressed to inject a bolus of autologous angiogenic agent into the myocardium at a location adjacent to channel C.

Advantageously, the needle stabilizer of device 41 permits an angiogenic agent to be injected at a location a predetermined distance from the channel formed by cutting head 48. By comparison, use of a separate needle catheter to inject an angiogenic agent into the myocardium after the channel forming process is completed would result in the angiogenic agent being injected at random locations relative to the previously formed channels.

As shown in FIG. 9C, a matrix of spaced-apart channels C and associated pockets of angiogenic agent may be formed in the wall of left ventricular wall LV by rotating outer guide catheter 42 and inner catheter 43 relative to one another (see FIG. 6). Needle stabilizer 59 and cutting head 48 are then advanced at each position to form further channels C in the tissue. The foregoing methods therefore enable a matrix of channels to be formed in the left ventricular wall. It is believed that such channels may be drilled anywhere on the walls of the heart chamber, including the septum, apex and left ventricular wall, and the above-

- 17 -

5 described apparatus provides this capability.

10

While preferred illustrative embodiments of the invention are described, it will be apparent that various changes and modifications may be made therein without departing from the invention, and the appended claims are intended to cover all such changes and modifications that fall within the true spirit and scope of the invention.

## - 18 -

#### What Is Claimed Is:

1. A method of performing percutaneous myocardial revascularization of a patient comprising: collecting autologous biological material from the patient;

preparing the autologous biological material to form an angiogenic agent;

providing a catheter adapted for insertion into the left ventricle comprising a hollow stabilizer element and a cutting head movable from a retracted position to an extended position;

advancing a distal region of the catheter transluminally to a position within the patient's left ventricle;

deploying the stabilizer element to stabilize the distal region of the catheter in contact with an endocardial surface;

advancing the cutting head from the retracted to the extended position to bore a channel into the patient's cardiac tissue; and

injecting an amount of the angiogenic agent through the hollow stabilizer needle into a region of the patient's cardiac tissue adjacent to the channel.

- 2. The method of claim 1 wherein the stabilizer element comprises a first retractable needle and deploying the stabilizer element comprises advancing the retractable needle to penetrate into the patient's cardiac tissue.
- 3. The method of claim 1 wherein collecting autologous biological material from the patient comprises collecting a quantity of whole blood from the patient.

- 19 -

- 4. The method of claim 1 wherein preparing the autologous biological material comprises centrifuging the whole blood to form a platelet-rich plasma.
- 5. The method of claim 4 wherein preparing the autologous material further comprises activating the platelet rich plasma.
- 6. The method of claim 5 wherein activating the platelet rich plasma further comprises activating the platelet rich plasma with purified thrombin.
- 7. The method of claim 1 wherein collecting autologous biological material from the patient comprises harvesting cells from the patient's cardiac tissue or bone marrow.
- 8. The method of claim 7 wherein preparing the autologous material further comprises culturing the harvested cells in vitro.
- 9. The method of claim 1 further comprising aspirating cardiac tissue severed by the cutting head.
- 10. The method of claim 1 further comprising, after the step of preparing an angiogenic agent, storing the angiogenic agent under refrigeration.
- 11. A method of performing percutaneous revascularization of a patient's cardiac tissue, the method comprising:

collecting autologous biological material

from the patient;

preparing the autologous biological material to form an angiogenic agent;

providing a catheter adapted for insertion into the left ventricle comprising a hollow needle movable from a retracted position to an extended position and a cutting head movable from a retracted position to an extended position;

advancing a distal region of the catheter transluminally to a position within a patient's left ventricle;

advancing the hollow needle to the extended position to penetrate and stabilize the distal region of the catheter in contact with an endocardial surface;

rotating the cutting head;


advancing the cutting head from the retracted to the extended position to bore a channel into the patient's cardiac tissue; and


injecting an amount of the angiogenic agent through the hollow needle into a region of the patient's cardiac tissue adjacent to the channel.


- 12. The method of claim 11 wherein injecting an amount of the angiogenic agent comprises injecting a predetermined bolus of angiogenic agent to form a pocket of angiogenic material adjacent to the channel.
- 13. The method of claim 11 wherein collecting autologous biological material from the patient comprises collecting a quantity of whole blood from the patient.


- 21 -


- 14. The method of claim 11 wherein preparing the autologous biological material comprises centrifuging the whole blood to form a platelet-rich plasma.
- 15. The method of claim 14 wherein preparing the autologous material further comprises activating the platelet rich plasma.
- 16. The method of claim 15 wherein activating the platelet rich plasma further comprises activating the platelet rich plasma with purified thrombin.
- 17. The method of claim 11 wherein collecting autologous biological material from the patient comprises harvesting cells from the patient's cardiac tissue or bone marrow.
- 18. The method of claim 17 wherein preparing the autologous material further comprises culturing the harvested cells in vitro.
- 19. The method of claim 11 further comprising aspirating cardiac tissue severed by the cutting head.
- 20. The method of claim 1 further comprising, after the step of preparing an angiogenic agent, storing the angiogenic agent under refrigeration.














# INTERNATIONAL SEARCH REPORT

International application No. PCT/US00/07274

CLAS	SIFICATION OF SUBJECT MATTER	
( )	A61B 17/00	·
JS CL :6	506/170 International Patent Classification (IPC) or to both national cl	lassification and IPC
	OS SEARCHED	
	cumentation searched (classification system followed by classi	ification symbols)
	06/1, 14, 46, 108, 159, 167, 170, 180	
ocumentati	on searched other than minimum documentation to the extent the	at such documents are included in the fields searched
ectronic d	ata base consulted during the international search (name of dat	a base and, where practicable, search terms used)
. DOC	UMENTS CONSIDERED TO BE RELEVANT	
ategory*	Citation of document, with indication, where appropriate,	of the relevant passages Relevant to claim No.
Λ	WO 96/35469 A (KESTEN et al.) 14 No document.	ovember 1996, entire 1-20
☐ Fu	orther documents are listed in the continuation of Box C.	See patent family annex.
<del></del>	Special categories of cited documents:  document defining the general state of the art which is not considered	later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention
•E"	to be of particular relevance earlier document published on or after the international filing date "X"	document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step
"Ľ.	document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other	when the document is taken alone
	special reason (as specified) document referring to an oral disclosure, use, exhibition or other means	considered to involve an inventive step when the documents are combined with one or more other such documents, such combination
"P"	document published prior to the international filing date but later than	being obvious to a person skilled in the art document member of the same patent family
\	the priority date claimed	
	the actual completion of the	of mailing of the international search report
04 M	AY 2000	() = A
Comm	na mailing address of the Israesissioner of Patents and Trademarks	WILLIAM LEWIS
Washi	ngton, D.C. 20231	ephone No. (703) 308-0060